

Part 1 General

1.1 SECTION INCLUDES

- .1 Electric leak detection system.
- .2 Monitoring grid.
- .3 Testing and measuring apparatus.

1.2 RELATED SECTIONS

- .1 Section 01 23 00 - Alternates.
- .2 Section 01 45 00 - Quality Control.
- .3 Section 07 33 63 - Vegetated Roofing.
- .4 Section [] - [] Roofing.
- .5 Section 07 55 52 - Modified Bituminous Protected Membrane Roofing.
- .6 Section [] - [].
- .7 Section 11 24 23 - Window Washing Equipment and Fall Protection.
- .8 Division 22 - Plumbing: Drains and scuppers.
- .9 Division 26 - Electrical: Data connection from system panel to building communications room.

1.3 ALTERNATES

- .1 Provide an alternate price for copper conductor cables in lieu of stainless steel conductor cables.

1.4 REFERENCES

- .1 RCABC (Roofing Contractors Association of British Columbia) Guarantee Corp. - RCABC Roofing Practices Manual.
- .2 Journal of ASTM International (Vol.8, No. 9) Paper ID- JAI 103772 - Electrical Conductance Methods for Locating Leaks in Roofing and Waterproof Membranes.

1.5 SYSTEM DESCRIPTION

- .1 Installation of permanent monitoring grid and access closure with related testing and measuring apparatus to facilitate detection of membrane leak locations. The leak locate function is performed at the grid access closure when manufacturer personnel on-site

[OR]

- .2 Performed by remote computer system connected by internet to the building intelligence monitoring center.

1.6 ADMINISTRATIVE REQUIREMENTS

- .1 Section 01 31 00: Project management and coordination procedures.
- .2 Coordination: Coordinate with other work having a direct bearing on work of this section.
- .3 Pre-installation Meeting: Convene four (4) weeks before starting work of membrane roofing.
 - .1 Review preparation and installation procedures and coordinating and scheduling required with related work.

1.7 SUBMITTALS

- .1 Section 01 33 00: Submission procedures.
- .2 Product Data: Provide manufacturer's data sheets for product components and accessories.

- .3 Shop Drawings: Indicate plans, grid layout, dimensions, construction details, methods of anchorage, location and type of roof penetrations and roof drains.
 - .1 Indicate location of access closures, wiring path from monitoring grids to access closures.
 - .2 Indicate location where grid cables will be terminated and area where monitoring electronics or future monitoring electronics will be installed.
 - .3 Indicate location of electrical guard circuits around drains.
- .4 Test Reports: Test reports from approved testing agency certifying that leak detection system conforms to performance characteristics and testing requirements specified.
- .5 Installation Data: Manufacturer's written installation requirements.
- .6 Test Protocol: Manufacturer's written description of testing method and protocol.

1.8 CLOSEOUT SUBMITTALS

- .1 Section 01 78 00: Submission procedures.
- .2 Operation and Maintenance Data: Indicate maintenance requirements for installed products.
- .3 Maintenance Service: Submit proposal to perform membrane integrity scans every three (3) months.

1.9 QUALITY ASSURANCE

- .1 Products to be listed as Accepted Materials in the RCABC Roofing Practices Manual.
- .2 Manufacturer Qualifications: Company specializing in manufacturing the Products specified in this Section with minimum three (3) years documented experience.
- .3 Manufacturer shall be ISO 9000 Certified.
- .4 Installer Qualifications: Company specializing in performing the work of this Section with minimum three (3) years documented experience and approved by the manufacturer.
- .5 Testing Agency Qualifications: Company specializing in performing the work of this Section with minimum three (3) years documented experience and approved by the manufacturer.

1.10 DELIVERY, STORAGE AND HANDLING

- .1 Section 01 60 00: Transport, handle, store, and protect products.
- .2 Protect electronic equipment and sensing and detection devices against potential damage from dust and moisture.

1.11 ENVIRONMENTAL REQUIREMENTS

- .1 Do not install leak detection system to damp or frozen surfaces or during inclement weather.
- .2 Do not perform scans when heavy rain is falling.

1.12 WARRANTY

- .1 Manufacturer's Warranty: Provide a two (2) year manufacturer's warranty to include coverage for failure to meet specified requirements.

Part 2 Products

2.1 MANUFACTURERS

- .1 SMT Research Ltd.: 778-373-2070 or 778-373-2071. www.smtresearch.ca

2.2 EQUIPMENT

- .1 DigiSCAN Power Supply: Voltage supply to induce electrical potential to the light layer of water on top of membrane relative to the roof deck below.

- .2 DigiSCAN Membrane Scanner: Digital Multi-vector 16 probe membrane scanning device which outputs the voltage magnitude and vector direction to the operator. Use of related head attachment for vertical scanning, and corners.
- .3 MultiSCAN board: Automated switching and measurement unit that facilitates the rapid connection to and testing of the monitoring grid installed on the top surface of waterproof membranes.

2.3 COMPONENTS

- .1 Moisture Detection Sensors: Type 316 stainless steel conductor cables; laminated tape construction with two cables and self adhering insulating substrate.
- .2 Access Closure: Metal box enclosure with space for cable terminations on terminal blocks and monitoring electronics and screw terminal barrier blocks for connecting grid cable and to provide field test access. Access closure to be watertight in exterior locations.
 - .1 Provide 400 x 350 x 150 mm deep (16 x 14 x 6 inches) box per 500 sq.m (5,400 sq.ft).
- .3 Electrical Cable and Accessories: As recommended by system manufacturer.

2.4 COMPONENTS (ALTERNATE PRICE)

- .1 Permanently Installed MultiSCAN Board and Building Intelligence Gateway (Alternate): Automated monitoring system for permanent installation to access closure for real-time monitoring of protected membrane grid system. Provide required MultiSCAN boards, on-site gateway and connection to internet system. Others to provide 110v power and internet connection at location of main access enclosure.

Part 3 Execution

3.1 EXAMINATION

- .1 Section 01 71 00: Verify existing conditions before starting work.
- .2 Verify that membrane penetrations are of a non-conductive material or are electrically isolated by applying applications of additional layers of non-conductive waterproof material or other electrically insulating materials.
- .3 Verify that the waterproof membrane extends above all overburden to avoid unintended electrical paths to ground.
- .4 Verify that a suitable liquid-applied or weatherproof insulating material or a cap sheet may be applied to insulate exposed concrete. Metal flashings and other metal elements should be clear of overburden and soil to achieve the electrical insulation and avoid unintended grounds.
- .5 Verify availability of hose and water supply of sufficient length to reach all points on surfaces to be surveyed.
- .6 Coordinate with responsible entity to correct unsatisfactory conditions.
- .7 Commencement of work by surveyor is acceptance of installation conditions.

3.2 PREPARATION

- .1 Membranes to be scanned to be broom clean (except for follow-up surveys on vegetated waterproofing) and are free of overburden, construction materials, equipment and debris.

3.3 INSTALLATION - MONITORING GRID

- .1 Install monitoring grid to manufacturer's written instructions and approved shop drawings.
- .2 Place a conductor with Type 316 stainless steel conductors in the specified pattern on top of waterproof membrane.
- .3 Space conductor wires in accordance with the table below for wet side monitoring grids.

Environment	Grid Spacing
Concrete Pavers	3 x 3 meters
Extensive Green Roof (up to 200 mm deep)	3 x 3 meters
Intensive Green Roof	2 x 2 meters
Concrete Topping	2 x 2 meters

- .4 Provide specific electronic guard around drains.

3.4 INSTALLATION - ACCESS CLOSURE

- .1 Install access closure to manufacturer's written instructions.
- .2 Install and terminate electrical cables from grid on approved screw terminal blocks or IDC connection blocks in access closure.

3.5 SURVEY PROCEDURE

- .1 Perform initial membrane scan to establish baseline conditions to equipment manufacturer's written requirements.
- .2 Verify wiring sequence, electrical continuity and the absence of shorts or grounds on grid system.
- .3 Perform test of leak detection system prior to installation of protection boards, drainage panels and other overburden.
- .4 DigiSCAN roof surfaces including inside and outside corners of parapets and equipment curbs. Use scanning equipment appropriate to the surfaces being scanned.
- .5 Mark breach locations on membrane with a marker approved by the waterproof membrane contractor and/or Inspector.
- .6 Record location of membrane breach on sketch or drawings for communication with contractor and/or inspector.
- .7 Perform final waterproof survey immediately following installation of final layer of inverted or vegetated roof with grid system.

3.6 FIELD QUALITY CONTROL

- .1 Section 01 45 00: Field inspection and testing.
- .2 Require site attendance of roofing manufacturer representative during installation of the Work.
- .3 Correct identified defects or irregularities.
- .4 Field Reports: Identify date, time, and weather conditions when surveys are conducted.
- .1 Provide general description of scan/survey equipment and process.
- .2 Describe typical membrane breaches located and areas not accessible by scanning equipment.
- .3 Document survey with photographs and plan view scale drawings with approximate location of breaches noted.

END OF SECTION 07 01 73